



South East Elevation



North West Elevation



North East Elevation



South West Elevation

**Schedule of Materials**

**Distribution Centre**

Roof  
 Profiled metal cladding panels in Goosewing Grey (HPS200 Finish) with Merlin Grey eaves fascia and soffit.

Walls  
 Generally - Vertically spanning profiled metal cladding panels for the main body of the building in Merlin Grey (HPS200 Finish) with vertical bands of horizontally spanning composite micro-rib metal panels in Silver (HPS200 Finish) and Green feature band above with horizontal spanning profiled metal cladding panels in Albatross Grey (HPS200 Finish) at high level.

Refrigeration Plant Space - Vertical bands of horizontally spanning composite micro-rib metal panels in Silver (HPS200 finish) with Silver louvres at upper level.

Personnel Doors  
 Metal faced flush doors painted Green.

Loading Doors  
 Insulated metal doors with PVDF2 outer finish in Silver / Merlin Grey.

**Offices**

Roof  
 Flat roof system to main offices and profiled metal cladding panels in Goosewing Grey (HPS200 Finish) to distribution offices with Merlin Grey eaves fascia and soffit.

Walls  
 Horizontally spanning composite micro-rib metal panels in Silver (HPS200 Finish).

Windows/Doors  
 PPC frames in graphite grey with grey tinted glazing and grey lookalike panel spandrels.

Entrance Lobby and Canopy  
 Profiled metal cladding panel roof in Goosewing Grey (HPS200 Finish) with Merlin Grey eaves soffit and fascia and Merlin Grey composite micro-rib metal panels in Merlin Grey (HPS200 Finish) above glazing.

no.	date	revision	by
A.	23/05/11	Two Level Plant Area developed & Main Office FE Stair 3 reconfigured; LV/ HV Plant & Generator base added adjacent Inbound Hub Offices	spp

aja architects llp  
 1170 Elliott Court  
 Herald Avenue  
 Coventry Business Park  
 COVENTRY CV5 6UB  
 E: aja@aja-architects.com  
 W: www.aja-architects.com

aja architects llp is a limited liability partnership registered in England No. OC328721  
 client



project  
**New C cross Dock  
 Distribution Centre  
 Matrix Park, Eaton Road  
 Chorley**

dra wing

**Proposed Elevations**

scale 1:400 drawn spp  
 checked date 18/05/11

no

5032 - 110 rev A